

Our standard installation included

– Supply labour & material to install split unit air conditioner complete with 10 feet 0.61mm thickness copper refrigerant pipe & 10mm thickness insulation, control cable from indoor to outdoor unit, 10 feet 15mm PVC drain pipe, outdoor unit install with steel bracket, testing & commissioning for the air conditioner.

Extra charges applied when

– Copper refrigerant pipe exceed standard air-conditioner installation piping 10 feet.

Extra copper refrigerant piping:

* 1.0HP RM 20.00/ft

* 1.5HP RM 22.00/ft

* 2.0HP RM 25.00/ft

* 2.5HP RM 28.00/ft

* 3.0HP RM 30.00/ft

* 3.5HP RM 32.00/ft

* 4.0HP RM 35.00/ft

* 5.0HP RM 38.00/ft

Supply & install power supply for air conditioner

– Supply & install air conditioner power supply from electric panel complete with 5 length 1" PVC casing/15mm PVC conduit pipe & 20 amps heater switch.

* **From** RM 200.00/unit

– Supply & install air conditioner power supply looping from nearest power sources in 1" PVC casing/15mm PVC conduit pipe & 20 amps heater switch.

* **From** RM 70.00/unit

Additional charges for PVC casing if needed

* 1" RM 10.00/length

* 1" x 2" RM 20.00/length

* 2" x 2" RM 40.00/length

* 2" x 3" RM 60.00/length

* 2" x 4" RM 80.00/length

Terms & Conditions

Remark:

– For any additional job on-site during installation, a separate quotation will be provided by our technician.

– Our pricing does not include coring, conceal work, patch up, repair & painting work (for ceiling, wall & floor), wiring/incoming power supply & control panel, unless specifically provided for above.

– Customer shall provide proper delivery/work venue & ensure the safety/well being of his/her/their own belongings/properties to which we shall not be liable for any damages caused during the said delivery/work.